1999年 9月17日 17時14分 オプトデバイス事業部 企画館

NO. 5431 P. 1

	*//	7 1 7 <del>1 7 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1</del>	·	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	J431 1, 1	
PREPARED BY:	DATE:	1	_/>	SPEC. No.	ED-99170	
00110		SHAF	SH/H	SS 2	August 30,	1999
J. Jakaoka Ulu	2 31. 1999	•		PAGE	9 Pag s	
APPROVED BY:	DATE:	ELECTRONIC COMP GROUP SHARP COR	:	REPRESENT	TARAL ITS	10
Tomorario a	9.31/997	SPECIFICA	ΓΙΟΝ	OPTO-ELEC	TRONIC DEV	recs biv.
Ur U		SPECIFICATION FOR				
		ISTANCE MEASURIN	G SENSOR		,	
, .	MODEL	OP2D120	,			
•		0120120	<del></del>			:
	••					
		ude materials protected und use anyone to reproduce the			on ("Sharp").	
in these specific for any damage	ation sheets, a resulting from	se observe the absolute max as well as the precautions m use of the product which do in these specification shocks	entioned below. pes not comply w	Sharp assumes with the absolute	s no responsibi e maximum rai	lity
(Precautions)			·		·	
	-	med for use in the following		_		
		· Audio visual equipment · · · on equipment (Terminal) · ·	• •			
If the	use of the pro	duct in the above applications sure to observe the precauti	n areas is for equ	uipment listed i		
	•	es, such as fail-safe design a	. •	• • • •	• •	
and sa	fety when this	he overall system and equip product is used for equipmed d precision, such as;				
		introl and safety equipment	faircraft, train, a	utomobile etc.)	7	
• Tra		Gas leakage sensor breaker				
		is product for equipment who and precision, such as ;	ich require extre	emely high relia	bility	
1		• Telecommunication equi ntrol equipment • Medical	•	( lines)		
		onsult with a Sharp sales rejion of the above three paragr		ere are any que	enolle	
1	- ,	h a Sharp sales representati	-	ions about this	product.	
OLIOTO MEDIC	Approtrat		DATE	_		
CUSTOMER'S	APPROVAL		PRESENTE	U · 7		1
			for K. Oza			<b>-</b>
DATE		a		ment General ering Dept., V	Manager of	
BY	and the second section of the sec	c-vacament introduce	Opto-E	elling Dept., v Electronic Devi OM Group	ces Div.	
			SHARP	CORPORATIO	NC	

1999年 9月17日 17時15分

オプトデバイス事業部 介面

## SHARP CORPORATION

ED-99170 August 30, 1999

MODEL No.

GP2D120 PAGE
1/9

### 1. Application

This specification applies to the outline and characteristics for analog output type distance measuring sensor, Model No. GP2D120.

#### 2. Outline

4

Refer to the attached drawing No. SOD03596.

## 3. Ratings and characteristics

- 3-1 Constitution diagram: Refer to the attached sheet, page 4.
- 3-2 Absolute maximum ratings: Refer to the attached sheet, page 4.
- 3-3 Electro-optical Characteristics: Refer to the attached sheet, page 5.
- 3-4 Timing chart: Refer to the attached sheet, page 5.

## 4. Reliability

Refer to the attached sheet, page 6.

## 5. Incoming inspection

Refer to the attached sheet, page 7.

## 6. Supplement

6-1 GP2D120 Example of Output distance characteristics

Refer to the attached sheet, page 8.

6-2 GP2D120 Example of output characteristics with inverse number of distance

Refer to the attached sheet, page 9.

## 6-3 ODS materials

This product shall not contain the following materials.

Also, the following materials shall not be used in the production process for this product.

Materials for ODS: CFC<sub>6</sub>. Halon, Carbon tetrachloride, 1.1.1-Trichloroethane (Methylchloroform)

## 6-4 Brominated flame retardants

Specific brominated flame retardants such as the PBBOs and PBBs are not used in this device at all.

6-5 Product mass: 3.6g (TYP.)

1999年 9月17日 17時15分

オプトデバイス事業的企画

NO. 5431 P. 3


### SHARP CORPORATION




#### 7. Notes

- 7-1 Lens of this device shall be kept cleanly. There are cases that dust, water or oil and so on deteriorate the characteristics of this device. Please consider in actual application.
- 7-2 In case that protection cover is set in front of the emitter and detector portion, the protection cover which has the most efficient transmittance at the emitting wavelength range of LED for the GP2D120 (λ =850nm±70nm), shall be recommended to use. The face and back of protection cover should be mirror polishing. Also, as there are cases that the characteristics may not be satisfied with according to the distance between the protection cover and the GP2D120 or the thickness of the protection cover; please use the GP2D120 after confirming the operation sufficiently in actual application.
- 7-3 In case that there is an object near to light exits of the sensor between the sensor and the detected object, please use this device after confirming sufficiently what the characteristics of this sensor do not change by the object.
- 7-4 When the detector surface receive direct light from the sun. Tungsten lamp and so on, there are cases that it can not measure the distance exactly. Please consider the design that the detector does not receive direct light from such light source.
- 7-5 Distance between sensor and mirror reflector can not sometimes measure exactly.


  In case of changing the mounting angle of the GP2D120, it may measure the distance exactly.
- 7-6 In case that reflective object has boundary line clearly, there is cases that distance can not measure exactly. At that time, if direction of boundary line and the line between emitter center and detector center parallels, it is possible to decrease deviation of measuring distance.



7-7 In order to decrease measuring error by moving direction of object, we recommend to mount the sensor like below drawing.




- 7-8 In order to stabilize power supply line, we recommend to connect a by-pass capacitor of  $10\,\mu F$  or more between Vcc and GND near the GP2D120.
- 7-9 Please don't do washing. Washing may deteriorate the characteristics of optical system and so on.
- 7-10 There are some possibilities that the sensor inside the case package with lens may be exposed to the excessive mechanical stress. Please be careful not to cause any excessive pressure on the case package with lens and also on the PCB at the assembly and inserting of the set.



オプトデバイス事業部 企画部

NO. 5431 P. 5



# 3-2 Absolute maximum ratings

LED

LED drive circuit

(Ta=25°C, Vcc=5V)

Parameter	Symbol	Rating	Unit	Remark
Supply voltage	Vec	-0.3 to +7	V	
Output terminal voltage	Vo	-0.3 to Vcc+0.3	v	
Operating temperature	Topr	-10 to +60	τ	
Storage temperature	Tstg	-40 to +70	τ	

Output circuit

Measuring distance IC

## Operating Supply Voltage

Parameter	Symbol	Rating	Unit	Remark
Operating Supply Voltage	Vcc	4.5 to 5.5	V	

1999年 9月17日 17時16分

オプトデバイス事業部 企画部

NO. 5431 P. 6

## SHARP CORPORATION


ED-99170 August 30, 1999
MODEL No. PAGE
6P2D120 5/9

## 3-3 Electro-optical Characteristics

Parameter	Symbol	Conditions		Min.	Тур.	Max.	Unit
Measuring distance range	ΔL		(*1)	4		30	cm
Output terminal voltage	Vo	L±30cm	(°,1)	0.25	0.4	0.55	V
Output voltage difference	ΔVo	Output change L change (30cm → 4cm)	at (*1)	1.95	2.25	2.55	V
Average supply current	lcc	L=30cm	(*1)	•	33	50	mA

- \* L: Distance to reflective object
- (\*1) Using reflective object: White paper (Made by Kodak Co. Ltd. gray cards R-27 · white face, reflective ratio: 90%)

## 3-4 Timing chart



1999年 9月17日 17時16分

オプトデバイス事業部 企画部

NO. 5431 P. 7

## **SHARP CORPORATION**

ED-99170 August 30, 1999
MODEL No. PAGE
GP2D120 6/9

### 4. Reliability

The reliability of products shall satisfy items listed below.

Confidence level: 90% LTPD: 20%/40%

No.	Test Items	Test Conditions	Failure Judgement Criteria	Samples (n) Defective(C)
1	Temperature cycling	1 cycle -40°C → +70°C (30min) (30min) 25 cycles test		n=11, C=0
2	High temp. and high humidity storage	+40°C,90%RH, 500h		n=11, C=0
3	High temp. storage	+70°C, 500h	Initial $\times$ 0.8 $>$ Vo	n=11, C=0
4	Low temp. storage	-40°C, 500h	Vo > initial $\times$ 1.2	n=11, C=0
5	Operation life (High temp.)	+60°C, Vcc=5V, 500h	(*1)	n=11, C=0
6	Mechanical shock	100m/s², 6.0ms 3times/±X, ±Y, ±Z direction		n=6,C=0
7	Variable frequency vibration	10 to 55 to 10Hz/1min Overall amplitude: 1.5mm 2h/X, Y, Z direction		n= 6 , C=0


- \*1 Test conditions are according to 3-3 Electro-optical characteristics.
- \*2 After test, measurement shall be measured after leaving under the normal temperature and the normal humidity for two hours. But, no dew point.

1999年 9月17日 17時17分

オプトデバイス事業部 企画部

NO. 5431 P. 8

## SHARP CORPORATION



- 5. Incoming inspection
  - (1) Inspection lot

Inspection shall be carried out per each delivery lot.

(2) Inspection method

A single sampling plan, normal inspection level || based on ISO 2859 shall be adopted.


Defect	Defect Inspection items and test method		
Major defect	Electro-optical characteristics defect (In para. 3-3)	0.4	
Minor defect	Defect on appearance and dimension  * Split, chip, scratch, stain	1.0	

One which affects the characteristics of para. 3-3 shall be defect.

SplitChipScratchStain

1999年 9月17日 17時17分 オプトデバイス事業部 企画部

NO. 5431 P. 9



1999年 9月17日 17時17分

オプトデバイス事業部 企画部

NO. 5431 P. 10

